

IMPACT CRUSHERS

Impact crushers, PF (70 - 250 t/h, cubical aggregate)

FACTORY DIRECT | IMPORT COSTS INCLUDED | 380 V

R1 488 628

Approximate · landed and cleared, collected from our Johannesburg warehouse. Confirmed on your quotation and fixed for its validity period.

Choose your model 2 available

◉ PF1214 impact crusher, 70 - 180 t/h, 132 kW	**R1 488 628**
○ PF1315 impact crusher, 90 - 250 t/h, 200 kW	**R1 922 372**

Made for your order, shipped by sea
Sea freight alone takes 35–45 days. We confirm the delivery date with the factory within one working day of your order.

Inspected by us, then collected or delivered
We check every order at our warehouse before it goes to you. Collect it free from our Johannesburg warehouse, or we deliver anywhere in South Africa and to neighbouring countries, and the delivery is charged at cost.

Pay only into our company account
Against a written quotation, into the Nedbank business account in the company's registered name.

Registered South African company
Tryg Enterprises (Pty) Ltd, reg. 2026/621598/07. Faulty goods are repaired, replaced or refunded: delivery, returns and warranty.

Ask on WhatsApp | Spec sheet (PDF)

Horizontal-shaft impact crushers for the secondary stage: a fast rotor throws the rock against impact plates, giving well-shaped, cubical aggregate for concrete and road building. Adjustable output size and replaceable blow bars.

SPECIFICATION

WHAT YOU ARE GETTING

PF1214	Rotor 1250 × 1400 mm, feed opening 755 × 1440 mm, max feed 140 mm, 70 - 180 t/h, 132 kW, 3545 × 2462 × 2640 mm, 18.6 t
PF1315	Rotor 1320 × 1500 mm, feed opening 855 × 1600 mm, max feed 160 mm, 90 - 250 t/h, 200 kW, 3591 × 3068 × 2975 mm, 28.3 t
Use	Secondary crushing of medium-hard rock (limestone, dolerite, recycled concrete) into cubical aggregate
Motor	Electric motor included in the price (380-400 V three-phase)
Complete lines	Feeder, jaw, cone or impact crusher and screen are sized together on one quote; a full line ships together, which brings the freight per machine down
Options	2 models below
PF1214 impact crusher, 70 - 180 t/h, 132 kW	approx R1,488,628
PF1315 impact crusher, 90 - 250 t/h, 200 kW	approx R1,922,372
Lead time	Confirmed on your quote (sea freight alone is 35-45 days)

Specifications are as supplied by the manufacturer and confirmed at inspection before shipping. Tell us the job and we will confirm this is the right machine for it, or say if it is not.

Prices are approximate, landed and cleared in South Africa; confirmed on your quotation and fixed for its validity period. Payment terms are on your quotation; pay only into our company account.

Tryg Enterprises (Pty) Ltd · Reg. 2026/621598/07 · 7 Wagen Road, Estcourt, KwaZulu-Natal, 3310 · sales@tryg.co.za · +27 68 940 7376