

VIBRATORY ROLLERS (WALK-BEHIND & RIDE-ON)

Ride-on road rollers, tandem vibratory (1 - 3 t)

FACTORY DIRECT | IMPORT COSTS INCLUDED

R170 555

Approximate · landed and cleared, collected from our Johannesburg warehouse. Confirmed on your quotation and fixed for its validity period.

Choose your model — 6 available

◉ FYL-880CC, 1 t, Changfa diesel 9 hp, 740 / 800 mm drums	**R170 555**
○ FYL-900CC, 1.5 t, Changfa diesel 12 hp, 900 mm drums	**R251 623**
○ FYL-1100, 3 t, Changchai diesel 34.5 hp, 1200 mm drums	**R405 985**
○ FYL-900, 1.5 t, Honda GX630 petrol 20 hp, Danfoss hydraulics	**R369 510**
○ FYL-900P, 1.5 t, Kubota diesel 25 hp, Poclain / Danfoss hydraulics	**R403 680**
○ FYL-1200, 3 t, Kubota diesel 35.5 hp, both drums vibrate, 0 - 12 km/h	**R693 013**

Made for your order: about 10–12 weeks
Built by the factory for your order, then shipped by sea to our warehouse, duties paid.

Inspected by us, then collected or delivered
We check every order at our warehouse before it goes to you. Collect it free from our Johannesburg warehouse, or we deliver anywhere in South Africa and

to neighbouring countries, and the delivery is charged at cost.

Pay only into our company account
Against a written quotation, into the Nedbank business account in the company's registered name.

Registered South African company
Tryg Enterprises (Pty) Ltd, reg. 2026/621598/07. Faulty goods are repaired, replaced or refunded: delivery, returns and warranty.

Ask on WhatsApp | Spec sheet (PDF)

Ride-on tandem rollers for roads, parking areas, paving and sports surfaces. Full hydraulic drive with stepless speed, both drums driven, hydraulic steering and vibration on the front drum (switchable to both drums on the FYL-1200), with big water tanks for asphalt. Diesel or Honda petrol, from 1 to 3 tonnes.

SPECIFICATION

WHAT YOU ARE GETTING

Drive	Full hydraulic, stepless (CVT), both drums driven; 0 - 5 to 0 - 12 km/h; 30 - 40% gradeability
Vibration	Hydraulic, 60 - 70 Hz, 25 - 60 kN
Water tank	60 - 200 L
Engines	Changfa or Changchai diesel (9 - 34.5 hp), Honda GX630 petrol (20 hp) or Kubota diesel (25 - 35.5 hp)
Drums	530 × 740 mm up to 700 × 1200 mm
Hydraulics	Danfoss / Poclain components on the FYL-900, FYL-900P and FYL-1200
Warranty	One year from the manufacturer
Options	6 models below
FYL-880CC, 1 t, Changfa diesel 9 hp, 740 / 800 mm drums	approx R170,555
FYL-900CC, 1.5 t, Changfa diesel 12 hp, 900 mm drums	approx R251,623
FYL-1100, 3 t, Changchai diesel 34.5 hp, 1200 mm drums	approx R405,985
FYL-900, 1.5 t, Honda GX630 petrol 20 hp, Danfoss hydraulics	approx R369,510

FYL-900P, 1.5 t, Kubota diesel 25 hp, Poclain / Danfoss hydraulics	approx R403,680
FYL-1200, 3 t, Kubota diesel 35.5 hp, both drums vibrate, 0 - 12 km/h	approx R693,013
Lead time	About 10-12 weeks: 15-20 working days to build, then sea freight (35-45 days) and clearing

Specifications are as supplied by the manufacturer and confirmed at inspection before shipping. Tell us the job and we will confirm this is the right machine for it, or say if it is not.

Spec sheet: Ride-on road rollers, tandem vibratory (1 - 3 t) · https://www.tryg.co.za/products/rollers-and-compactors

Prices are approximate, landed and cleared in South Africa; confirmed on your quotation and fixed for its validity period. Payment terms are on your quotation; pay only into our company account.

Tryg Enterprises (Pty) Ltd · Reg. 2026/621598/07 · 7 Wagen Road, Estcourt, KwaZulu-Natal, 3310 · sales@tryg.co.za · +27 68 940 7376